



Production Truck Dimensions

- Overall Length = 36'
- Overall Height = 13.5'
- Production Box Length = 24'
- GVWR: 33,000 lbs.
- Overall Truck Width = 9'

Equipment

- (6) Sony HXC-100 Triax HD Cameras w/Fujinon 72x, Canon 75x, (Canon 40x & Wide Angle, on request)
- Sony MVS-3000A 32-Input 2 M/E HD Switcher w/multiple keys & DME
- (4) AJA FS-1 Frame Synchronizers w/UP/DOWN/CROSS conversion
- (2) Blackmagic Design Teranex 2D video processors
- Harris Predator Multiviewer
- Chyron Mosaic HD Dual-channel CG w/Clip Player
- Blackmagic Design Universal VideoHub 56x56 HD Router, w/Fiber Optic I/O
- Matrox VS4 Quad HD recording server
- (6) KiPRO Rack HD Recorders, more available
- Playback Pro Plus for Quicktime file playback
- Behringer X32 40x16 audio console w/DANTE' card
- DBX 166 XL Stereo Compressor/Limiters
- Audio/Video Alignment Delay: Rane Digital AVA 22 D
- Gentner Digital Telephone Hybrids
- Clearcom PICO Matrix Intercom System w/ IFB, telephone, and 2-way radio interfaces
- RF & Fiber optic packages, Robotic cams, RF comms, Cammate 26' Jib and other equipment available upon request

Power Requirements

190-270 Volts AC, Single Phase, 100 Amps. We carry 150 ft of CamLok cable, with pigtails.

